BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/RD/WORK_INDENT17819/CALL-2

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/06/2015-16, Date:22.02.2016

Improvements to Roads and Drains at Balaji Layout Surroundings in Ward No. 08, Kodigehalli Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of M RAJASHEKAR		
				In Figures		In Words
1	180	1321 Hire charges of 100 KVA generator including operator, fuel, transportation and handling charges PWD SR 2013-14, P. L, I. 92 for pumping of stagnated water in existisng drain	hr	520	93600.00	Rupees Five Hundred Twenty Only
2	1399.29	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	cum	85	118939.65	Rupees Eighty Five Only
3	180.8	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding wherever necessary, sorting the dismantled material, disposal of unservicea ble material and stacking the serviceable material with all lifts complete as per specifications.- Rubble stone masonry in cement mortar	cum	1250	226000.00	Rupees One Thousand Two Hundred Fifty Only
4	18.34	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding wherever necessary, sorting the dismantled material, disposal of unservicea ble material and stacking the serviceable material with all lifts complete as per specifications. - RCC grade M20 and above	cum	1200	22008.00	Rupees One Thousand Two Hundred Only
5	5978.07	Removing B.S Slab of Drain and stackin	sqm	65	388574.55	Rupees Sixty Five Only
6	785.44	Construction of embankment with approved material deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Table 300-2 complete as per specifications which includes watering charges and compaction	cum	190	149233.60	Rupees One Hundred Ninety Only
7	4184.64	Refixing stone slabs of drains and pointing in C.M (1:3)	sqm	110	460310.40	Rupees One Hundred Ten Only
8	1793.43	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete - 10.0 cms thic	sqm	950	1703758.50	Rupees Nine Hundred Fifty Only
9	243.94	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications	Cum	5320	1297760.80	Rupees Five Thousand Three Hundred Twenty Only
10	126.56	Providing and constructing granite / trap / basalt size stone masonry in superstructure with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications	cum	3900	493584.00	Rupees Three Thousand Nine Hundred Only
11	34.15	With New stones	cum	5300	180995.00	Rupees Five Thousand Three Hundred Only
12	714.27	Providing ruled pointing to coursed stone masonry with cement mortar 1:4, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications cement mortar 1:4	sqm	100	71427.00	Rupees One Hundred Only

M-Rajashekar

H.V. Engg.
ಕ.ಅ. (ಬ್ರ.ಪ.) 20/7/16

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of M RAJASHEKAR		
				In Figures		In Words
13	62.86	KSRB 4-1.7 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.84 cum and fine aggregates @ 0.56 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications	cum	5460	343215.60	Rupees Five Thousand Four Hundred Sixty Only
14	48.9	Providing and constructing precast concrete solid blocks with compressive strength not less than 3.5 N/sqmm with CM 1:4 masonry with solid concrete blocks of size 40x20x20 cm conforming to IS 2185 / 1965 in superstructure including cost of all materilas, labour charges, scaffolding, curing complete as per specifications.	sqm	1240	60636.00	Rupees One Thousand Two Hundred Forty Only
15	1388.53	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km etc complete as per specifications and directions of engineer in charge of the work	Cum	80	111082.40	Rupees Eighty Only
					5721125.50	

M. Rajashekar
Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92
20/7/16

20/07